



Insulation Proposal Workspace

Build accurate residential insulation proposals in minutes.

Contractor: CARLOS EDUARDO VIEIRA DE MATOS
Company: thermInsu
Status flow: draft → sent

Create Proposal

draft

Search homeowner

Gemini

Gemini

Search service area

Type to search service areas

DOE climate zone

Cool (Zone 5)▼

Attic (Floor)
1.100 sq ft · Cellulose

Remove

Basement
950 sq ft · Fiberglass

Remove

Crawl Space
350 sq ft · Fiberglass

Remove

Rim Joists
200 sq ft · Spray Foam

Remove

Garage Ceiling
450 sq ft · Fiberglass

Remove

Material

Fiberglass▼

Application

Batts (Manta)▼

Proposal Preview

draft

ThermaShield Insulation - Insulation Proposal

Customer: Gemini

Location: Framingham, MA

Zone: Cool (Zone 5)

Attic (Floor)

\$7,600.71

Scope of Work	Preparation, air sealing, and insulation for Attic (Floor)
Preparation	Remove existing debris and install 25 baffles
Air Sealing	Seal all penetrations using fire-rated foam
Insulation	Install Cellulose using Blown-in (Soprado)
Target	R-60 (existing R-11, install R-49)
Added Depth	13.24 inches
Area	1.100 sq ft
Material quantity	53.90 bags
Air Sealing	\$500.00
Baffle Installation	\$375.00

Basement

\$5,183.21

Scope of Work	Preparation, air sealing, and insulation for Basement
Preparation	Remove existing debris and prep the area
Air Sealing	Seal all penetrations using fire-rated foam
Insulation	Install Fiberglass using Batts (Manta)
Target	R-30 (existing R-0, install R-30)

Material R-value / inch

3,2

Application unit

sq ft

Service area (sq ft)

450

Waste factor (%)

10

Existing insulation (R-value)

0

Target R-value

30

R-value to install

30

Material (\$/sq ft)

1,65

Labor (\$/sq ft)

1,2

Coverage factor

1

Mobilization (\$)

150

Margin (%)

30,0

Effective area (sq ft)

495

Depth (in)

9,38

Estimated material (sq ft)

495

Search additional scope

Type part of the scope name

Air Sealing

flat ·

\$500.00 ·

total

\$500.00

1

500

Remove

Subtotal (\$)

2060,75

Suggested total (\$)

2943,93

Final total (\$)

2943,93

Use Formula

Use Suggestion

Match Suggested

Service line note

Poorly installed R-11 fiberglass.

Added Depth	9.38 inches
Area	950 sq ft
Material quantity	1045.00 sq ft
Air Sealing	\$500.00
<i>Note Need wire supports to ensure it doesn't fall over due to humidity.</i>	
Crawl Space \$2,496.07	
Scope of Work	Preparation, air sealing, and insulation for Crawl Space
Preparation	Remove existing debris and prep the area
Air Sealing	Seal all penetrations using fire-rated foam
Insulation	Install Fiberglass using Batts (Manta)
Target	R-21 (existing R-0, install R-21)
Added Depth	6.56 inches
Area	350 sq ft
Material quantity	385.00 sq ft
Air Sealing	\$500.00
<i>Note Critical Service: Vapor Barrier (6-mil or 10-mil vapor barrier on the ground).</i>	
Rim Joists \$2,892.86	
Scope of Work	Preparation, air sealing, and insulation for Rim Joists
Preparation	Remove existing debris and prep the area
Air Sealing	Seal all penetrations using fire-rated foam
Insulation	Install Spray Foam using Spray Foam (Closed Cell)
Target	R-21 (existing R-0, install R-21)
Added Depth	3.23 inches
Area	200 sq ft
Material quantity	710.60 board feet
Air Sealing	\$500.00
<i>Note This is the area where I feel the strongest cold drafts.</i>	
Garage Ceiling \$2,943.93	

General proposal note

General project notes (e.g., 'Includes installation and cleanup')

Selected line: Garage Ceiling

Scope of Work	Preparation, air sealing, and insulation for Garage Ceiling
Preparation	Remove existing debris and prep the area
Air Sealing	Seal all penetrations using fire-rated foam
Insulation	Install Fiberglass using Batts (Manta)
Target	R-30 (existing R-0, install R-30)
Added Depth	9.38 inches
Area	450 sq ft
Material quantity	495.00 sq ft
Air Sealing	\$500.00
Note	Poorly installed R-11 fiberglass.

Investment: Subtotal	\$21,116.78
Estimated Federal Tax Credit (30%, max \$1,200)	- \$1,200.00
Net Investment (after tax credit)	\$19,916.78

Move to Sent

Cancel Proposal